



Eriskay Outtake - Case Study



Contract: Eriskay Outfall

Client: Scottish Water

Contract Duration: 3 Weeks

Contract Value: >£30,000



Installation of replacement outfall pipe. The works were required to work with the tide timetable . With limited shift times available to pour concrete. A section of the outfall was removed via hydraulic breaker and replaced with new shutter and concreted.

The shuttering in sea conditions had to be built for purpose and with the short shift times we decided to hire in Piri Shuttering, this worked out extremely well, as it allowed all the shutter to be installed and left to the elements. This allowed the concrete to be poured in one shift (4 hours) were 25m³ was produced and poured.



Summary



MacAulay Askernish successfully completed the works on schedule. The ability to produce concrete in the short time frame was hugely advantages.